

Asbestos Register

(Hazardous Materials and Risk Assessment)

School : Greystanes High School (8385)
Region : Western Sydney
State Electorate : Prospect
Local Government Area : Holroyd

Initial Survey : Noel Arnold & Associates : 28 - Mar - 2008
Reviewed By : Parsons Brinckerhoff : 28 - May - 2015



2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00A - General Learning/Science Learning - 1963 - Brick/Block (Brick/Block)**Exterior**

Wall Cladding	Compressed AC Sheet 8385/B00A/Wall Cladding/S6					No Asbestos Detected
Eaves Linings	Flat AC Sheeting 8385/B00E/Eaves Linings/S23	60m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Sun Shades	Compressed AC Sheet 8385/B00A/Sun Shades/S24	30m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Ceiling Voids	No Asbestos Found					
Underfloor Voids	No Asbestos Found					

Interior**B00A - R0001 - Laboratory L.S. (86.24 m2)**

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00A - R0002 - General Storeroom (9.21 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

Floor Coverings Res/Textile	Vinyl Tiles 8385/B00A/R0002/Floor Coverings Res/Textile/S4					No Asbestos Detected
-----------------------------	---------------------------------------------------------------	--	--	--	--	-----------------------------

B00A - R0006 - General Learning Space (72.23 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00A - R0007 - Staff Study (25.14 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00A - R0008 - Staff - Toilet (5.98 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00A - R0009 - General Storeroom (5.29 m2)

No Asbestos

B00A - R0010 - Movement (116.89 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00A - R0011 - Food Technology L.S. (66.49 m2)

No Asbestos

B00A - R0018 - Distribution Board Cupboard (1.04 m2)

No Asbestos

Note: No inspection of live electrical installation.

B00A - R0021 - Cleaning Store - Distributed (12.17 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00A - R0022 - Stairs (4.67 m2)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
No Asbestos						
B00A - R0023 - Pantry/Preparation (17.64 m2)						
No Asbestos						
B00A - R0024 - Laundry (5.86 m2)						
No Asbestos						
B00A - R0025 - Pantry (4.44 m2)						
No Asbestos						
B00A - R0026 - Stairs (4.67 m2)						
No Asbestos						
B00A - R0027 - Staff Study (42 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken
Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works						
B00A - R0028 - Food Technology L.S. (100.65 m2)						
No Asbestos						
B00A - R0029 - General Learning Space (37.81 m2)						
No Asbestos						
B00A - R1001 - General Learning Space (53.16 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1006 - General Learning Space (52.44 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1007 - General Learning Space (52.29 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1008 - Staff Study (25.28 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1009 - Staff - Toilet (6.03 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1010 - Cleaning Store - Distributed (5.34 m2)						
No Asbestos						
B00A - R1011 - Movement (111.17 m2)						
Wall Linings Internal	Flat AC Sheeting	60m2	Upper portion	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00E/R1006/Wall Linings Internal/S27					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1012 - General Learning Space (39.87 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)
B00A - R1013 - General Learning Space (65.44 m2)						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00A - R1014 - Resource/Project Store (3.23 m2)						
Floor Coverings Res/Textile	Vinyl Tiles					
8385/B00A/R0002/Floor Coverings Res/Textile/S4				No Asbestos Detected		
B00A - R1015 - G.L.S. Store (2.98 m2)						
Floor Coverings Res/Textile	Vinyl Tiles					
8385/B00A/R0002/Floor Coverings Res/Textile/S4				No Asbestos Detected		
B00A - R1016 - Materials Store (5.99 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	1m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
Floor Coverings Res/Textile	Vinyl Tiles					
8385/B00A/R0002/Floor Coverings Res/Textile/S4				No Asbestos Detected		
B00A - R1017 - Materials Technology L.S. (65.73 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00A - R1018 - Design L.S. (51.65 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00A - R1019 - Materials Store (6.5 m2)						
No Asbestos						
B00A - R1020 - Cleaning Store - Distributed (5.34 m2)						
No Asbestos						
B00A - R1021 - Stairs (7.58 m2)						
No Asbestos						
B00A - R1022 - Stairs (7.57 m2)						
No Asbestos						
B00A - R1024 - Staff Kitchen (4.6 m2)						
Recently Modified Space	Requires Inspection					
B00A - R1025 - Staff Study (47.51 m2)						
Recently Modified Space	Requires Inspection					



Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00B - Pupil Facilities - 1963 - Brick/Block (Brick/Block)**Exterior**

Ceiling Voids	No Asbestos Found					
Underfloor Voids	No Asbestos Found					
Gable Ends	Compressed AC Sheet	12m2	North & South (x4 locations)	Minimal Damage (2)	Low (1)	Low Priority (2-3)
	8385/B00B/Gable Ends/S25			Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)		

Interior**B00B - R0001 - Toilets-Boys (89.77 m2)**

No Asbestos

B00B - R0002 - Shower/Change (46.74 m2)

No Asbestos

B00B - R0003 - Shower/Change (12.25 m2)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00B/R0003/Partition Walls (Cubicles)/S7			No Asbestos Detected		

B00B - R0004 - Staff Shower (9.89 m2)

No Asbestos

B00B - R0005 - Distribution Board Cupboard (0.46 m2)

Note: No inspection of live electrical installation.

Electrical Mounting Board	Resinous Board	1Unit	East	Good Condition (1)	Low (1)	Low Priority (2-3)
---------------------------	----------------	-------	------	--------------------	---------	--------------------

Assumed Asbestos - Electrical Hazard - Unable to access**B00B - R0006 - No Access (8.75 m2)**

No Asbestos

B00B - R0007 - Movement (6.16 m2)

No Asbestos

B00B - R0008 - Student Drinking Facilities (19.41 m2)

No Asbestos

B00B - R0009 - Sport Equipment Store (9.93 m2)

No Asbestos

B00B - R0010 - Office/Store (10.94 m2)

No Asbestos

B00B - R0011 - Movement (326.69 m2)

No Asbestos

B00B - R0012 - Student Canteen (52.43 m2)

No Asbestos

B00B - R0013 - Sport Equipment Store (17.79 m2)

No Asbestos

B00B - R0014 - Staff - Toilet (3.84 m2)

In-fill-panel	Flat AC Sheeting					
	8385/B00B/R0014/In-fill-panel/S8			No Asbestos Detected		

B00B - R0015 - Movement (6.08 m2)

Ceiling Structures/Linings	Flat AC Sheeting					
	8385/B00B/R0014/In-fill-panel/S8			No Asbestos Detected		

B00B - R0016 - Student Drinking Facilities (19.16 m2)

No Asbestos

B00B - R0017 - Sport Equipment Store (11.92 m2)

No Asbestos

B00B - R0018 - General Storeroom (11.41 m2)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Floor Coverings Res/Textile	Vinyl Tiles	12m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00B/R0018/Floor Coverings Res/Textile/S9					Chrysotile (white asbestos)	
B00B - R0019 - Shower/Change (11.54 m2)						
Partition Walls (Cubicles)	Compressed AC Sheet					
8385/B00B/R0003/Partition Walls (Cubicles)/S7					No Asbestos Detected	
B00B - R0020 - Shower/Change (43.31 m2)						
No Asbestos						
B00B - R0021 - Toilets-Girls (93.2 m2)						
No Asbestos						
B00B - R0022 - Movement (4.44 m2)						
No Asbestos						
B00B - R0023 - Cleaning Store - Distributed (5.11 m2)						
Ceiling Structures/Linings	Flat AC Sheeting					
8385/B00B/R0014/In-fill-panel/S8					No Asbestos Detected	
B00B - R0024 - Movement (4.65 m2)						
No Asbestos						
B00B - R0025 - Staff - Toilet (2.36 m2)						
No Asbestos						
B00B - R0026 - Office/Store (4.44 m2)						
No Asbestos						

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00C - Technological & Applied Studies - 1963 - Brick/Block (Brick/Block)**Exterior**

Eaves Linings	Flat AC Sheeting	50m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00E/Eaves Linings/S23					Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Ceiling Voids	No Asbestos Found					
Underfloor Voids	No Asbestos Found					

Interior**B00C - R0003 - Materials Technology L.S. (78.37 m2)**

Ceiling Structures/Linings	Flat AC Sheeting	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R0004 - Dust Extraction Space (4.37 m2)

No Asbestos

B00C - R0005 - Materials Store (13.41 m2)

Ceiling Structures/Linings	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R0006 - Materials Store (13.36 m2)

Ceiling Structures/Linings	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R0007 - Dust Extraction Space (4.17 m2)

No Asbestos

B00C - R0008 - Distribution Board Cupboard (0.84 m2)

Note: No inspection of live electrical installation.

No Asbestos

B00C - R0009 - Materials Technology L.S. (79.3 m2)

Ceiling Structures/Linings	Flat AC Sheeting	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R0011 - Materials Technology L.S. (75.08 m2)

Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00B/R0003/Partition Walls (Cubicles)/S7					No Asbestos Detected

B00C - R0012 - Materials Store (15.57 m2)

Ceiling Structures/Linings	Flat AC Sheeting	2m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00A/R1018/Ceiling Structures/Linings/S5					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R0015 - General Storeroom (17.18 m2)

No Asbestos

B00C - R0016 - Staff - Toilet (1.41 m2)

No Asbestos

B00C - R0017 - Cleaning Store - Distributed (3.57 m2)

No Asbestos

B00C - R0018 - Movement (102.81 m2)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No						Test Result

Floor Coverings Res/Textile	Vinyl Tiles					
	8385/B00A/R0002/Floor Coverings Res/Textile/S4					No Asbestos Detected

Wall Linings Internal	Flat AC Sheeting	60m2	Upper portion	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00E/R1006/Wall Linings Internal/S27					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R0019 - Computer Learning Space (38.87 m2)

No Asbestos

B00C - R0020 - Metal Technology Bay (78.84 m2)

No Asbestos

B00C - R0021 - Welding Area (4.17 m2)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00C/R0023/Partition Walls (Cubicles)/S28					No Asbestos Detected

B00C - R0022 - Welding Area (3.8 m2)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00C/R0023/Partition Walls (Cubicles)/S28					No Asbestos Detected

B00C - R0023 - Welding Area (1.82 m2)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00C/R0023/Partition Walls (Cubicles)/S28					No Asbestos Detected

B00C - R0024 - Movement (3.34 m2)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00C/R0023/Partition Walls (Cubicles)/S28					No Asbestos Detected

B00C - R0025 - Metal Technology Bay (13.44 m2)

Partition Walls (Cubicles)	Compressed AC Sheet					
	8385/B00C/R0023/Partition Walls (Cubicles)/S28					No Asbestos Detected

B00C - R0026 - Staff Study (66 m2)

Recently Modified Space Requires Inspection

B00C - R9001 - Main Switchroom (6.46 m2)

Electrical Mounting Board	Resinous Board	2Unit	South	Good Condition (1)	Low (1)	Low Priority (2-3)
	8385/B00C/R9001/Electrical Mounting Board/S29					Chrysotile (white asbestos)

B00C - R9002 - General Storeroom (21.64 m2)

Toilet Cistern	Fibre Cement Casting (Monocrete)	1Unit	West	Some Damage - Unsealed (3)	Low (1)	Medium Priority (4-5)
	8385/B00C/R9002/Toilet Cistern/S32					Chrysotile (white asbestos) , Amosite (brown asbestos)

B00C - R9003 - Garden Store Room (45.45 m2)

No Asbestos

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00D - Various - 1963 - Brick/Block (Brick/Block)**Exterior**

Wall Cladding	Compressed AC Sheet 8385/B00A/Wall Cladding/S6					No Asbestos Detected
Eaves Linings	Flat AC Sheeting 8385/B00E/Eaves Linings/S23	60m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Sun Shades	Compressed AC Sheet 8385/B00A/Sun Shades/S24	30m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Ceiling Voids	No Asbestos Found					
Underfloor Voids	No Asbestos Found					

Interior**B00D - R0001 - General Storeroom (12.17 m2)**

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0002 - General Learning Space (51.28 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0003 - General Learning Space (52.29 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0004 - Staff Kitchen (17.05 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0005 - Clinic - Boys (20.95 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0006 - Staff - Toilet (9.25 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0010 - Staff - Toilet (9.82 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00D - R0017 - Staff - Toilet (3.15 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

Floor Coverings Res/Textile	Vinyl Sheet 8385/B00D/R0018/Floor Coverings Res/Textile/S17					No Asbestos Detected
-----------------------------	----------------------------------------------------------------	--	--	--	--	-----------------------------

B00D - R0018 - General Storeroom (4.34 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Floor Coverings Res/Textile	Vinyl Sheet	8385/B00D/R0018/Floor Coverings Res/Textile/S17				No Asbestos Detected
B00D - R0019 - Cleaning Store - Distributed (2.89 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0020 - Distribution Board Cupboard (1.46 m2)					Note: No inspection of live electrical installation.	
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0021 - Deputy Principal (25.57 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0022 - Art Learning Space (52.29 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0023 - Art Learning Space (51.93 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0024 - Visual Arts Workshop (16.78 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0025 - Visual Arts Store (8 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0026 - Movement (74.42 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0027 - Stairs (5.04 m2)						
No Asbestos						
B00D - R0028 - Clinic-Waiting (16.88 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0029 - Interview/Office - Type 1 (11.86 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0030 - Administration - Clerical (6.99 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0031 - Deputy Principal Office (21.01 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0032 - Movement (43.84 m2)						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
No Asbestos						
B00D - R0033 - Public Entry (35.78 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
Floor Coverings Res/Textile	Vinyl Tiles	8385/B00D/R0034/Floor Coverings Res/Textile/S16				No Asbestos Detected
B00D - R0034 - General Storeroom (16.1 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
Floor Coverings Res/Textile	Vinyl Tiles	8385/B00D/R0034/Floor Coverings Res/Textile/S16				No Asbestos Detected
B00D - R0035 - Stairs (1.39 m2)						
No Asbestos						
B00D - R0036 - Chair Store (11.49 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
Floor Coverings Res/Textile	Vinyl Tiles	8385/B00D/R0034/Floor Coverings Res/Textile/S16				No Asbestos Detected
B00D - R0037 - Administration - Clerical (64.41 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R0038 - Principal Office (26.99 m2)						
Ceiling Structures/Linings	Vermiculite	8385/B00A/R0021/Ceiling Structures/Linings/S3				Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00D - R1001 - General Learning Space (53.09 m2)						
No Asbestos						
B00D - R1002 - General Learning Space (52 m2)						
No Asbestos						
B00D - R1006 - Staff - Toilet (4.81 m2)						
No Asbestos						
B00D - R1007 - Cleaning Store - Distributed (6.42 m2)						
No Asbestos						
B00D - R1008 - Movement (105.53 m2)						
No Asbestos						
B00D - R1009 - Movement (37.61 m2)						
No Asbestos						
B00D - R1010 - General Learning Space (52.95 m2)						
No Asbestos						
B00D - R1011 - General Learning Space (65.49 m2)						
No Asbestos						
B00D - R1012 - General Storeroom (9.11 m2)						
No Asbestos						
B00D - R1013 - Cleaning Store - Distributed (2.86 m2)						
No Asbestos						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
B00D - R1014 - Music Learning Space (52.58 m2)						
No Asbestos						
B00D - R1015 - Music Store (12.33 m2)						
No Asbestos						
B00D - R1016 - Music Learning Space (66.36 m2)						
No Asbestos						
B00D - R1017 - Staff Study (64.66 m2)						
No Asbestos						
B00D - R1018 - General Storeroom (12.64 m2)						
No Asbestos						
B00D - R1019 - General Learning Space (52.08 m2)						
No Asbestos						
B00D - R1020 - Stairs (18.61 m2)						
No Asbestos						
B00D - R1021 - Stairs (8.21 m2)						
No Asbestos						

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No				Test Result		

B00E - General Learning/Science Learning - 1963 - Brick/Block (Brick/Block)**Exterior**

Wall Cladding	Compressed AC Sheet 8385/B00A/Wall Cladding/S6					No Asbestos Detected
Eaves Linings	Flat AC Sheeting 8385/B00E/Eaves Linings/S23	60m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Sun Shades	Compressed AC Sheet 8385/B00A/Sun Shades/S24	30m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos) , Crocidolite (blue asbestos)
Ceiling Voids	No Asbestos Found					
Underfloor Voids	No Asbestos Found					

Interior**B00E - R0001 - General Storeroom (5.21 m2)**

No Asbestos

B00E - R0002 - Movement (122.3 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0003 - General Learning Space (52.87 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0004 - General Learning Space (52.01 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0005 - General Learning Space (52 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0006 - General Learning Space (52.01 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0007 - Staff Study (25.14 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0008 - General Storeroom (5.26 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0010 - General Learning Space (52.72 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0011 - Laboratory L.S. (85.23 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	--------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00E - R0012 - Preparation (34.24 m2)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00E - R0013 - Cleaning Store - Distributed (2.95 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00E - R0014 - Distribution Board Cupboard (0.73 m2)					Note: No inspection of live electrical installation.	
Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00E - R0015 - Laboratory L.S. (85.95 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00A/R0021/Ceiling Structures/Linings/S3					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00E - R0016 - Stairs (2.66 m2)						
No Asbestos						
B00E - R0017 - Stairs (5.05 m2)						
No Asbestos						
B00E - R0018 - General Storeroom (3.78 m2)						
No Asbestos						
B00E - R0019 - Staff - Toilet (1.78 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00E/R0019/Ceiling Structures/Linings/S31					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00E - R1001 - General Learning Space (52.87 m2)						
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00A/R1018/Ceiling Structures/Linings/S5	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) <i>Chrysotile (white asbestos) , Amosite (brown asbestos)</i>
B00E - R1002 - General Learning Space (52.15 m2)						
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00A/R1018/Ceiling Structures/Linings/S5	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) <i>Chrysotile (white asbestos) , Amosite (brown asbestos)</i>
B00E - R1003 - General Learning Space (52.01 m2)						
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00A/R1018/Ceiling Structures/Linings/S5	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) <i>Chrysotile (white asbestos) , Amosite (brown asbestos)</i>
B00E - R1004 - General Learning Space (52.01 m2)						
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00A/R1018/Ceiling Structures/Linings/S5	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) <i>Chrysotile (white asbestos) , Amosite (brown asbestos)</i>
B00E - R1005 - General Learning Space (52.72 m2)						
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00A/R1018/Ceiling Structures/Linings/S5	3m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) <i>Chrysotile (white asbestos) , Amosite (brown asbestos)</i>
B00E - R1006 - Movement (114 m2)						
Wall Linings Internal	Flat AC Sheeting 8385/B00E/R1006/Wall Linings Internal/S27	60m2	Upper portion	Good Condition (1)	Low (1)	Low Priority (2-3) <i>Chrysotile (white asbestos) , Amosite (brown asbestos)</i>
B00E - R1007 - General Learning Space (52.87 m2)						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00E - R1008 - General Learning Space (52.15 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00E - R1009 - General Learning Space (52.15 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00E - R1010 - Staff Study (51.72 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00E - R1011 - Staff Study (25.28 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00E - R1012 - Cleaning Store - Distributed (6.17 m2)						
No Asbestos						
B00E - R1013 - Staff - Toilet (4.74 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	3m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00A/R1018/Ceiling Structures/Linings/S5				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00E - R1014 - Stairs (6.73 m2)						
No Asbestos						
B00E - R1015 - Stairs (13.01 m2)						
No Asbestos						

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00F - Multi Purpose Facilities - 1982 - Brick/Block (Brick/Block)

Exterior

Ceiling Voids	No Asbestos Found
Underfloor Voids	No Asbestos Found

Interior

B00F - M0001 - Control Room (15.4 m2)

No Asbestos

B00F - R0001 - Chair Store (19.49 m2)

No Asbestos

B00F - R0002 - Staff - Toilet (1.79 m2)

No Asbestos

B00F - R0003 - Movement (4.61 m2)

No Asbestos

B00F - R0004 - Stage (110.91 m2)

No Asbestos

B00F - R0005 - Movement (4.45 m2)

No Asbestos

B00F - R0006 - Chair Store (21.82 m2)

No Asbestos

B00F - R0007 - Multi-Purpose Space (454.87 m2)

No Asbestos

B00F - R0008 - Toilets-Boys (26.73 m2)

Partition Walls (Cubicles)	Compressed AC Sheet	12m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)
----------------------------	---------------------	------	------	--------------------	---------	--------------------

8385/B00F/R0016/Partition Walls (Cubicles)/S19

Chrysotile (white asbestos)

B00F - R0009 - Student Canteen (17.57 m2)

No Asbestos

B00F - R0010 - Entry (69.36 m2)

No Asbestos

B00F - R0011 - Administration - Clerical (1.49 m2)

No Asbestos

B00F - R0012 - General Storeroom (5.76 m2)

Floor Coverings Res/Textile	Vinyl Tiles					No Asbestos Detected
8385/B00F/R0012/Floor Coverings Res/Textile/S18						

B00F - R0013 - General Storeroom (6.16 m2)

Floor Coverings Res/Textile	Vinyl Tiles					No Asbestos Detected
8385/B00F/R0012/Floor Coverings Res/Textile/S18						

Stormwater pipe (Within wall)	Fibre Cement Pipe	4m	South-West	Some Damage - Unsealed (3)	Low (1)	Medium Priority (4-5)
8385/B00F/R0013/Stormwater pipe (Within wall)/S26				Chrysotile (white asbestos) , Amosite (brown asbestos)		

B00F - R0014 - Distribution Board Cupboard (1.14 m2)

Note: No inspection of live electrical installation.

No Asbestos

B00F - R0015 - Cleaning Store - Distributed (2.64 m2)

Floor Coverings Res/Textile	Vinyl Tiles					No Asbestos Detected
8385/B00F/R0012/Floor Coverings Res/Textile/S18						

B00F - R0016 - Toilets-Girls (26.71 m2)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Partition Walls (Cubicles)	Compressed AC Sheet	12m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00F/R0016/Partition Walls (Cubicles)/S19					Chrysotile (white asbestos)	

B00F - R0017 - Movement (16.6 m2)

No Asbestos

B00F - R0018 - Movement (2.72 m2)

No Asbestos

B00F - R0019 - Movement (2.94 m2)

No Asbestos

B00F - R0020 - Movement (1.66 m2)

No Asbestos

B00F - R0021 - Movement (2.94 m2)

No Asbestos

B00F - R0022 - Movement (2.71 m2)

No Asbestos

B00F - R1001 - Performing Arts Changeroom (20.36 m2)

Floor Coverings Res/Textile Vinyl Tiles

8385/B00F/R0012/Floor Coverings Res/Textile/S18 **No Asbestos Detected**

B00F - R1002 - Movement (3.76 m2)

No Asbestos

B00F - R1003 - Movement (3.59 m2)

No Asbestos

B00F - R1004 - Performing Arts Changeroom (20.52 m2)

Floor Coverings Res/Textile Vinyl Tiles

8385/B00F/R0012/Floor Coverings Res/Textile/S18 **No Asbestos Detected**

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00G - Science/General Learning - 1974 - Brick/Block (Brick/Block)

Exterior

Wall Cladding	Compressed AC Sheet 8385/B00G/Wall Cladding/S15	76m2	Variable positions	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos)
Eaves Linings	Flat AC Sheeting 8385/B00G/Eaves Linings/S22					No Asbestos Detected
Ceiling Voids	No Asbestos Found					
Underfloor Voids	No Asbestos Found					

Interior

B00G - R0001 - Toilets-Boys (31.92 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
Partition Walls (Cubicles)	Compressed AC Sheet 8385/B00G/R0001/Partition Walls (Cubicles)/S12	8m2	North	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos)

B00G - R0002 - Distribution Board Cupboard (0.68 m2)

Note: No inspection of live electrical installation.

Wall Linings Internal	Flat AC Sheeting 8385/B00G/R1029/Wall Linings Internal/S14	4m2	East	Minimal Damage (2)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works

B00G - R0003 - Cleaning Store - Distributed (4.47 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	---------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00G - R0004 - Cleaning Supplies Store (2.27 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	---------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00G - R0005 - Cleaning Supplies Store (18 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00E/R0019/Ceiling Structures/Linings/S31					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
----------------------------	---------------------------------------------------------------	--	--	--	--	-----------------------------------------------------------------------------------------------------------------------------------------------------

B00G - R0006 - Laboratory L.S. (100.62 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
Fume Cupboard	Flat AC Sheeting 8385/B00G/R0009/Fume Cupboard/S11	1Unit	East	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos)

B00G - R0009 - Laboratory L.S. (92.78 m2)

Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works
Fume Cupboard	Flat AC Sheeting 8385/B00G/R0009/Fume Cupboard/S11	1Unit	West	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos)

B00G - R0010 - General Storeroom (6.09 m2)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No				Test Result		
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0011 - G.L.S. Store (6.16 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0012 - General Learning Space (60.41 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0013 - Darkroom Space (25.42 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0014 - General Storeroom (2.94 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0015 - General Storeroom (8.94 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0016 - Distribution Board Cupboard (0.74 m2) Note: No inspection of live electrical installation.						
Wall Linings Internal	Flat AC Sheeting 8385/B00G/R1029/Wall Linings Internal/S14	4m2	West	Minimal Damage (2)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0017 - Staff - Toilet (3.94 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0018 - Security Store (8.05 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0020 - General Storeroom (6.16 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0026 - Laboratory L.S. (100.35 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
Fume Cupboard	Flat AC Sheeting 8385/B00G/R0009/Fume Cupboard/S11	1Unit	East	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos)
B00G - R0027 - Movement (247.37 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R0028 - Preparation - Science (11.19 m2)						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
No Asbestos						
B00G - R0029 - Apparatus Store (13.38 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0030 - Chemical Store (11.87 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0031 - Performing Arts Changeroom (6.09 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0032 - Staff Room (74.07 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0033 - Movement (81.73 m2)						
No Asbestos						
B00G - R0034 - Stairs (5.01 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0035 - Stairs (5.19 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0036 - Staff Study (39.31 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00E/R0019/Ceiling Structures/Linings/S31			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0037 - Preparation - Science (39.49 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00E/R0019/Ceiling Structures/Linings/S31			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R0038 - Staff Kitchen (3.11 m2)						
Recently Modified Space	Requires Inspection					
B00G - R0039 - Staff Study (49.53 m2)						
Recently Modified Space	Requires Inspection					
B00G - R1001 - Staff Room Annexe (33.6 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1007 - G.L.S. Store (6.12 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1008 - Art Learning Space (52.29 m2)						
Ceiling Structures/Linings	Vermiculite		8385/B00G/R0012/Ceiling Structures/Linings/S10			Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1009 - Art Learning Space (52.29 m2)						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1010 - General Storeroom (3.83 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1011 - Bulk Store (6.12 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1012 - Deputy Principal Office (16.97 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1013 - Administration - Clerical (10.05 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1014 - Movement (6.21 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1016 - Special Education Support Centre (26.46 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1017 - Distribution Board Cupboard (0.71 m2)						
				Note: No inspection of live electrical installation.		
Wall Linings Internal	Flat AC Sheeting	4m2	West	Minimal Damage (2)	Low (1)	Low Priority (2-3)
	8385/B00G/R1029/Wall Linings Internal/S14					Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1018 - Staff - Toilet (3.97 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1019 - General Learning Space (60.39 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1020 - G.L.S. Store (6.05 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1021 - G.L.S. Store (6.05 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						
B00G - R1022 - General Learning Space (52.58 m2)						
Ceiling Structures/Linings	Vermiculite					
	8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken
<i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>						

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No				Test Result		
B00G - R1023 - General Learning Space (52.58 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1024 - Special Learning Space (52.58 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1025 - G.L.S. Store (6.12 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1026 - G.L.S. Store (6.09 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1027 - General Learning Space (60.25 m2)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet) 8385/B00G/R1043/Floor Coverings Res/Textile/S30	61m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos)
Ceiling Structures/Linings	Vermiculite 8385/B00E/R0019/Ceiling Structures/Linings/S31					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1028 - Toilets-Girls (32.81 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1029 - Distribution Board Cupboard (0.71 m2) Note: No inspection of live electrical installation.						
Wall Linings Internal	Flat AC Sheeting 8385/B00G/R1029/Wall Linings Internal/S14	4m2	East	Minimal Damage (2)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1030 - Cleaning Store - Distributed (4.44 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1032 - Ancillary Staff (15.32 m2)						
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00G/R1041/Ceiling Structures/Linings/S13	16m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos)
B00G - R1033 - Stairs (7.84 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
B00G - R1034 - Administration - Clerical (21.27 m2)						
Ceiling Structures/Linings	Vermiculite 8385/B00G/R0012/Ceiling Structures/Linings/S10					Limited Samples Taken <i>Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works</i>
Ceiling Structures/Linings	Flat AC Sheeting 8385/B00G/R1041/Ceiling Structures/Linings/S13	10m2	West	Good Condition (1)	Low (1)	Low Priority (2-3) Chrysotile (white asbestos) , Amosite (brown asbestos)

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	
B00G - R1035 - Movement (224.43 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	225m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00G/R1041/Ceiling Structures/Linings/S13				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00G - R1036 - Staff Study (12.75 m2)						
Ceiling Structures/Linings	Vermiculite					
8385/B00G/R0012/Ceiling Structures/Linings/S10				Limited Samples Taken		
Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works						
B00G - R1037 - General Storeroom (6.03 m2)						
Ceiling Structures/Linings	Vermiculite					
8385/B00G/R0012/Ceiling Structures/Linings/S10				Limited Samples Taken		
Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works						
B00G - R1039 - Special Education Support Centre (11.1 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	12m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00G/R1041/Ceiling Structures/Linings/S13				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00G - R1040 - Stairs (7.84 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	8m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00G/R1041/Ceiling Structures/Linings/S13				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00G - R1041 - General Storeroom (13.86 m2)						
Ceiling Structures/Linings	Flat AC Sheeting	14m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00G/R1041/Ceiling Structures/Linings/S13				Chrysotile (white asbestos) , Amosite (brown asbestos)		
B00G - R1042 - Special Education Support Centre (55.37 m2)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	56m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00G/R1043/Floor Coverings Res/Textile/S30				Chrysotile (white asbestos)		
Ceiling Structures/Linings	Vermiculite					
8385/B00E/R0019/Ceiling Structures/Linings/S31				Limited Samples Taken		
Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works						
B00G - R1043 - Staff Study (37.01 m2)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	37m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)
8385/B00G/R1043/Floor Coverings Res/Textile/S30				Chrysotile (white asbestos)		
Ceiling Structures/Linings	Vermiculite					
8385/B00E/R0019/Ceiling Structures/Linings/S31				Limited Samples Taken		
Vermiculite Ceilings may contain asbestos. Asbestos testing MUST be conducted prior to any disturbance works						

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

B00H - Library - 1963 - Brick/Block (Brick/Block)

Exterior

Ceiling Voids	No Asbestos Found
Underfloor Voids	No Asbestos Found

Interior

B00H - R0001 - Security Store (4.82 m2)

Ceiling Structures/Linings	Flat AC Sheeting 8385/B00H/R0001/Ceiling Structures/Linings/S21	No Asbestos Detected
----------------------------	--------------------------------------------------------------------	-----------------------------

B00H - R0002 - Audio Visual Workroom (34.65 m2)

No Asbestos

B00H - R0003 - Workroom (40.38 m2)

No Asbestos

B00H - R0004 - Librarian (11.78 m2)

No Asbestos

B00H - R0006 - Staff - Toilet (2.4 m2)

No Asbestos

B00H - R0007 - Staff - Toilet (2.4 m2)

No Asbestos

B00H - R0008 - Distribution Board Cupboard (1.05 m2)

Note: No inspection of live electrical installation.

Ceiling Structures/Linings	Flat AC Sheeting 8385/B00H/R0008/Ceiling Structures/Linings/S20	No Asbestos Detected
----------------------------	--------------------------------------------------------------------	-----------------------------

Wall Linings Internal	Flat AC Sheeting 8385/B00H/R0008/Ceiling Structures/Linings/S20	No Asbestos Detected
-----------------------	--------------------------------------------------------------------	-----------------------------

B00H - R0009 - Cleaning Store - Distributed (1.05 m2)

No Asbestos

B00H - R0010 - Seminar (13.4 m2)

No Asbestos

B00H - R0011 - Senior Study (20.71 m2)

No Asbestos

B00H - R0013 - General Storeroom (7.71 m2)

No Asbestos

B00H - R0014 - Entry (7.74 m2)

No Asbestos

B00H - R0015 - Main Area (336.23 m2)

No Asbestos

B00H - R0016 - Senior Study (63.77 m2)

No Asbestos

B00H - R0017 - Plant (8.77 m2)

No Asbestos

B00H - R0018 - Plant (9.25 m2)

No Asbestos



Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

Demountables

There are no Demountable(s) located at this school as per the AMS records as of 15 Feb 2017.

2017

Product	Material Description	Extent	Location Reference	Material Condition	Risk Status	Control Priority
Sample No					Test Result	

Listing of Electronic Attachments as of 22/03/2017

There are no asbestos related file attachment(s) for this school.

2017